WS 10-23-02



CITY COUNCIL WORK SESSION ON EISENHOWER-TO-DUKE STREET CONNECTOR

WEDNESDAY, OCTOBER 23, 2002 5:30 P.M. COUNCIL CHAMBERS

AGENDA

- I. INTRODUCTION
- II. STAFF PRESENTATION
 - A. Review of No Build and Build Alternatives
 - B. Staff Recommendation
- III. COUNCIL DISCUSSION

Individuals with disabilities who require assistance or special arrangements to participate in the City Council Work Session may call the City Clerk and Clerk of Council's Office at 703-838-4500 (TTY/TDD 703-838-5056). We request that you provide a 48-hour notice so that the proper arrangements may be made.



Eisenhower Avenue to Duke Street Connector

City Council Work Session October 23, 2002



Agenda

- Overview
- Task Force Accomplishments
- Review of Findings
- Staff Recommendations
- Discussion



Background

1973 &	Council requests new interchange at
1980	Clermont Avenue
1984	FHWA approves Clermont Interchange
1987	FHWA rejects request to terminate project at Eisenhower Avenue
1993	Environmental review completed
1997	Clermont Interchange opened to traffic
2001	Council creates Task Force to re-study Eisenhower-to-Duke Connector




Current Issues

- 1. Should the City proceed with a connector roadway between Eisenhower Avenue and Duke Street?
- 2. If so, what location(s) should be carried forward to the next phase environmental review?



Next Steps



Eisenhower-to-Duke Connector



Project Objectives

"To improve access and ease traffic congestion along the Eisenhower Avenue and Duke Street corridors to meet current and future traffic demands while minimizing visual and environmental impacts and avoiding degradation of neighborhoods."



Task Force Accomplishments

- Developed objective and purpose
- Reviewed inventory information
- Developed preliminary alternates
- Selected candidate alternates
- Participated in citizens meeting
- Directed survey for 2nd public meeting



Task Force Accomplishments (continued)

- Selected decision criteria
- Identified data and analyses needs
- Compiled data and analysis results
- Created summary matrix
- Voted "Build" vs. "No Build" Alternates



Task Force Votes

No Build	7	VS.	No Build w/ Imp	7
No Build	11	VS.	Alternate D	3
No Build w/ Imp	9	VS.	Alternate D	5
No Build	9	VS.	Alternate C	5
No Build w/ Imp	9	VS.	Alternate C	5
No Build	9	VS.	Alternate B-1	5
No Build w/ Imp	9	VS.	Alternate B-1	5



Staff Findings




Guiding Principles

- Keep traffic on the arterials
- Drivers select routes based on
 - Time
 - Distance
 - Convenience
- Local trips have priority over through trips
- Increase effectiveness of roadway network




Connectors Serve Significant Travel Demand






Sources of Connector Traffic






Connectors Reduce Traffic on Van Dorn and Telegraph



Alternate



Connectors Improve Balance of Interchange Demands





Connectors Improve Traffic Conditions on Area Roadways


Change in Average Delay at Signalized Intersections

Roadway	No Build	No Build w/ Imp	Alts A1/A2	Alt B1	Alt B2	Alt C	Alt D
Duke Street	Base	-62%	-62%	-55%	-60%	-61%	-54%
Van Dorn Stre	et Base	-64%	8%	-44%	-45%	-29%	-24%
Eisenhower Ave	nu € ase	-84%	-70%	-57%	-51%	-41%	-54%
Seminary Roa Janney's Lan	d/ Base	-20%	-3%	-11%	-15%	-7%	-29%



Connectors Improve Traffic Conditions on Area Roadways

Average Network Travel Delay





Connectors Improve Traffic Conditions on Area Roadways

2020 Traffic Queues at Selected Intersections


		M	aximum	Queue	e Lengt	h (feet)
Intersection	Directio	n No Build	No Build w/ Imp	Alt A1/A2	Alt B1/B2	Alt C	Alt D
Duke at Daingerfield	EB	1,542	1,542	1,400	1,141	600	600
Duke at Telegraph	EB	3,540	1,180	2,222	1,130	1,040	1,010
North Quaker at Duke	SB	1,746	216	497	429	300	290
Van Dorn at Edsall	SB	580	104	579	535	348	524
Van Dorn at South Picke	tt SB	176	25	164	112	143	179

^{1.} EB = eastbound, SB = southbound

^{2.} All data for PM peak period, except Duke at Daingerfield which is AM peak period




Connectors Increase Connectivity



Eisenhower-to-Duke Connector




Connectors Increase Connectivity



Eisenhower-to-Duke Connector




Benefits of Connectivity



"From a transportation standpoint [street] **grid systems** provide an almost infinite number of paths between various points. It therefore tends to distribute traffic over the network rather than concentrating it on a few facilities."



Connectors Enhance Public Safety



Eisenhower-to-Duke Connector



Connectors Enhance Public Safety

Change in Emergency Response Time (minutes)

Response times for Stations 207 and 208 to central points in west Eisenhower Valley



Connectors Do Not Adversely Impact Neighborhood Residential Streets

2020 Potential Cut-Through Traffic Volume

	Potential Cut-Through Traffic (vehicles-per hour)									
Roadway	No Build	No Build w/ Imp.	Alts A1/A2	Alts B1/B2	Alt C	Alt D1				
West Taylor Run	430	780	310	350	200	420				
Cambridge	130	20	120	110	80	40				
Ft. Williams	120	80	190	190	50	40				
Jordan	290	340	500	360	450	140				

^{1.} No through movements are permitted between Connector Alternative D and Cambridge



Connectors Serve Alexandria Traffic

2020 Connector Traffic

C	No Build	No Build w/ Imp.	Alts A1/A2	Alts B1/B2	Alt C	Alt D1
Internal to Study Area	N/A	N/A	43%	33%	24%	34%
Internal to Alexandria	N/A	N/A	65%	62%	67%	70%

Study area includes both original and expanded study areas as defined in the Technical Report



Connectors Serve Alexandria Traffic

2020 Traffic on North Quaker Lane

	Existing	No Build	No Build w/ Imp.	Alts A1/A2	Alts B1/B2	Alt C	Alt D1
Internal to Study Area	N/A	57%	56%	57%	56%	57%	57%
Internal to Alexandria	55%	66%	65%	66%	65%	66%	67%
Average Daily Traffic	22,000	28,500	30,200	28,500	32,900	31,500	32,000
Volume External to Alexandria	9,900	9,700	10,700	9,800	11,500	10,600	10,600
Percent Change	Base	-2%	8%	-1%	16%	7%	7%

Study area includes both original and expanded study areas as defined in the Technical Report



Estimated Construction Costs

Altarmata		Estimated Cost	
Alternate	Right-of-Way ²	Construction ³	Total
No Build	0	0	0
No Build w/ lmp.	\$17,000,000	\$38,000,000	\$55,000,000
Alternate A1	8,100,000	26,900,000	35,000,000
Alternate A2	16,600,000	19,000,000	35,600,000
Alternate B1	500,000	33,000,000	33,500,000
Alternate B2	500,000	35,200,000	35,700,000
Alternate C	3,000,000	15,700,000	18,700,000
Alternate D	5,800,000	19,000,000	24,800,000

^{1.} All costs in 2002 dollars

^{2.} Right-of-way includes land (\$1,000,000 per acre), value of improvements and relocation

^{3.} Construction costs include 25% contingency





Summary Matrix - September, 2002

Criteria		No Baild	lmprove Exist. Align	Alt AI	Alt A2	Alt Bi	An Bi
Truffic Service	- 2020			1.		er Frank	
ADF Reduction on Telegra ADT Reduction on V Reduction in Pelay - V Reduction in Delay - Dul Reduction in Unserved	an Dorn an Dorn te Street	:	• • • •	0	•0•0• • •0•0	000••	@O@••
Reduction in Queue Length - EB Duke @ f Reduction in Queue Length - SB Quaker Reduction in Queue Length - SB Van Dona & Growth in External - External North Potential increase in Cut	@ Dake } Edsall Chaker	• • • • • • • • • • • • • • • • • • • •	•000•	⊕O.₩O.@	00.00	00000	00000
Natural Enviro	pament					Program.	
Weilan Permitting C Acres of fore Acres in Fl Acres within 100° waterway Stream C	sts taken nodplale 'butter'	000000	000000	0 0 0 •	000	0000•	000000
Socia-Economic l	Jenefils	•					
Chango in einergency response time to P Ersenhower Change in emergency response time to Pe Eisenhower Community facilities within ½ mile o Bicycle or general use truits c	Location int West Location f termini	•	•	0 00	000	0 00	. 0 00
Socio-Economic	mpacts						
Acres of Pa Park activities Number of usiden Number of busines Number of sensitive noiso receptot	mpacted ses taken ses taken	00000	00	• 0000	000•0	• 000	• OOO
Cultural Ro	sources						
Potential för archeological Known archeological sites wi Registered historic résources withi	thin 100'	000	000	000	000	. O.	• • • •
Engineering and Estimat	ed Casts		."				
Consumo Right of ' Length on existing	Vay Cost	000		⊕	9	• 0 0	

Task Force Summary Matrix



Summary of Benefits

				Alter	nate			
Criteria	No Build	No Build w/ Imp	A1	A2	В1	B2	C	D
Traffic Service Benefits								
ADT reduction - Telegraph	?	?	?	?	?	?	?	?
ADT reduction - Van Dorn	?	?	?	?	?	?	?	?
Balanced interchange demand	?	?	?	?	?	?	?	?
Delay reduction - Network	?	?	?	?	?	?	?	?
Delay reduction – Van Dorn	?	?	?	?	?	?	?	?
Delay reduction - Duke	?	?	?	?	?	?	?	?
Service to East Eisenhower	?	?	?	?	?	?	?	?
Service to external traffic	?	?	?	?	?	?	?	?
Potential for cut-through traffic	· ?	?	?	?	?	?	?	?
Completion of roadway grid	?	?	?	?	?	?	?	?
Socio-Economic Benefits	-1.5							
Public safety response time	?	?	?	?	?	?	?	?
Community facilities served	?	?	?	?	?	?	?	?
Trails connected	?	?	?	?	?	?	?	?
Connectivity to Eisenhower	?	?	?	?	?	?	?	?



Summary of Impacts

				Alter	nate			
Criteria	No Build	No Build w/ Imp	A 1	A2	B1	B2	C	D
Natural Environment Impacts								
Wetland impacts	?	?	?	?	?	?	?	?
Permit challenges	?	?	?	?	?	?	?	?
Forest impacts	?	?	?	?	?	?	?	?
Floodplain impacts	?	?	?	?	?	?	?	?
RPA and stream crossings	?	?	?	?	?	?	?	?
Socio-Economic Impacts								
Impacts to park land	?	?	?	?	?	?	?	?
Impacts to park activities	?	?	?	?	?	?	?	?
Proximity to noise receptors	?	?	?	?	?	?	?	?
Residential takings	?	?	?	?	?	?	?	?
Commercial takings	?	?	?	?	?	?	?	?
Cultural Resource Impacts								
Historic/prehistoric resources	?	?	?	?	?	?	?	?
Archaeological sites	?	?	?	?	?	?	?	?
Listed/eligible historic sites	?	?	?	?	?	?	?	?
Construction Costs and Impacts								
Construction cost	?	?	?	?	?	?	?	?
Right of way cost	?	?	?	?	?	?	?	?
Disruption of existing traffic	?	?	?	?	?	?	?	?



Ranking of Alternates - Benefits

	Cultonia		21200		Alter	nate			
Criteria	Criteria Weight	No Build	No Build w/ Imp	A1	A2	B 1	B2	С	D
Traffic Service Benefits	65	10	147	260	262	477	477	305	245
ADT reduction - Telegraph	6	0	-3	2	2	5	4	8	7
ADT reduction - Van Dorn	6	0	-3	9	9	8	7	3	3
Balanced interchange demand	12	0	0	5	5	10	9	2	2
Delay reduction - Network	12	0	5	2	2	8	9	5	3
Delay reduction - Van Dorn	5	0	9	0	0	7	7	3	3
Delay reduction - Duke	6	0	7	7	7	5	7	7	4
Service to East Eisenhower	4	0	5	2	2	4	4	5	6
Service to external traffic	2	5	0	8	9	3	3	5	5
Potential for cut-through traffic	4	0	4	5	5	6	6	7	7
Completion of roadway grid	8	0	0	3	3	9	9	5	3
Socio-Economic Benefits	35	0	35	136	136	244	262	248	250
Public safety response time	16	0	0	5	5	8	8	9	8
Community facilities served	6	0	0	3	3	4	5	4	7
Trails connected	6	0	0	4	4	6	8	4	4
Connectivity to Eisenhower	7	0	5	2	2	8	8	88	8



Ranking of Alternates - Impacts

Criteria	Coltonio	Alternate							
	Criteria Weight	No Build	No Build w/ Imp	A1	A2	B1	В2	C	D
Natural Environment Impacts	23	230	190	110	140	120	110	230	230
Wetland impacts	7	10	10	10	10	10	10	10	10
Permit challenges	2	10	5	0	5	5	5	10	10
Forest impacts	6	10	5	5	10	5	5	10	10
Floodplain impacts	2	10	10	5	0	5	0	10	10
RPA and stream crossings	6	10	10	0	0	0	0	10	10
Socio-Economic Impacts	37	370	290	245	365	198	185	286	328
Impacts to park land	8	10	10	3	10	1	0	10	10
Impacts to park activities	8	10	10	8	10	0	0	10	10
Proximity to noise receptors	5	10	10	9	9	6	5	6	8
Residential takings	8	10	10	10	10	10	10	10	10
Commercial takings	8	10	0	4	10	10	10	2	6
Cultural Resource Impacts	17	170	140	140	140	115	115	115	140
Historic/prehistoric resources	6	10	5	5	5	5	5	5	5
Archaeological sites	5	10	10	10	10	5	5	5	10
Listed/eligible historic sites	6	10	10	10	10	10	10	10	10
Construction Costs and Impacts	23	230	0	152	120	169	168	152	137
Construction cost	8	10	0	8	8	5	4	8	7
Right of way cost	8	10	0	4	0	10	10	4	4
Disruption of existing traffic	7	10	0	8	8	7	8	8	7
Total Points		1010	802	1043	1163	1323	1317	1336	1330

Eisenhower-to-Duke Connector



The City should proceed with a connector between Eisenhower Avenue and Duke Street because ...



A connector improves traffic movement on existing roadways

- Makes travel easier for Alexandrians
- Reduces delay and congestion
- Reduces through traffic in neighborhoods
- Minimizes potential cut-through traffic



A connector improves connectivity between two major arterials

- Additional access to and egress from Eisenhower Valley
- Roadway grid increases the efficiency of existing roadways
- Makes travel more convenient



A connector enhances public safety

- More options for police, fire and EMS
- Reduces response times
- Eliminates need to use non-roadway routes



A connector helps neighborhoods by encouraging vehicles to travel on major roadways.

- Cut-through primarily caused by delay and congestion on arterials and collectors
- Connector reduces delay and congestion on major roadways



A connector relieves congestion at the Telegraph Road and Van Dorn Street interchanges

- Use of Clermont interchange is increased significantly
- Demand at Telegraph and Van Dorn interchanges is reduced
- Future improvements may be avoided or minimized



A connector supports the economic vitality of Alexandria

- Eisenhower Valley is more accessible
- Travel between the Valley and the rest of Alexandria is easier
- Residential, employment and social / recreational opportunities are more accessible



A connector does not attract a significant amount of new traffic to Alexandria roadways; nor does it increase significantly the amount of traffic cutting through Alexandria.



Recommendations

- Select B1 as the preferred build alternate
- 2. Select D as the back-up preferred build alternate
- 3. Authorize staff to proceed with environmental study





Eisenhower-to-Duke Connector